

LOT IO RP 860722

PROPOSED AMENITIES BUILDING ISAAC MOORE PARK, KENILWORTH **SUNSHINE COAST REGIONAL COUNCIL STRUCTURAL DRAWINGS**

SCHEDULE OF STRUCTURAL DRAWINGS

DWG	DESCRIPTION
5576 03 S 100	SITE PLAN & DRAWING SCHEDULE
5576 03 S 110	GENERAL NOTES
5576 03 S 200	FOOTING & SLAB PLAN
5576 03 S 210	FOOTING & SLAB DETAILS
5576 03 S 211	FOOTING & SLAB DETAILS
5576 03 S 300	GROUND LEVEL WALLS AND FIRST LEVEL SUSPENDED SLAB PLAN
5576 03 S 310	SUSPENDED SLAB DETAILS
5576 03 S 400	FIRST & UPPER LEVEL WALLS AND ROOF PLANS
5576 03 S 410	TYPICAL SECTION
5576 03 S 420	WALL FRAMING DETAILS
5576 03 S 421	WALL FRAMING DETAILS
5576 03 S 500	ELEVATED WALKWAY FRAMING PLAN
5576 03 S 510	WALKWAY FRAMING DETAILS

1RP860722 EUMUNDI KENILWORTH ROAD **EXISTING BBQ** SHELTER PROPOSED **AMENITIES** SERVICE ROAD

SCALE 1:1000




PROPOSED AMENITIES BUILDING ISAAC MOORE PARK, KENILWORTH SUNSHINE COAST REGIONAL COUNCIL

SITE PLAN **SCHEDULE OF DRAWINGS**


PRELIMINARY ISSUE FOR REPORT ONLY

...... 5576 03 S 100


OM Agenda Page 251 of 340 **Sunshine Coast Regional Council**




TYPICAL SITE DRAINAGE LAYOUT



DRAINAGE LAYOUT FOR WET SITES



SURFACE DRAINS ALONG LINE OF SLOPES



DRAINAGE LAYOUT FOR CUT AND FILL SITES

ENSURE SITE DRAINAGE IS MAINTAINED DURING AND POST CONSTRUCTION

GENERAL NOTES:

- These drawings shall be read in conjunction with all other consultants drawings and specifications. Before proceeding with the works any discrepancies in the engineering drawings shall be referred for decision to the Engineer. Setting out dimensions and sizes of members or elements shall not be obtained by scaling the drawings.
- All dimensions shown on the engineering drawings shall be checked by the contractor before commencement
- of fabrication or site works.

 During construction, the structure shall be maintained in a stable condition. Construction loads must not exceed the safe load capacity of the structure at any time during construction. If in doubt ask the Engineer. All workmanship and materials shall be in accordance the requirements of the current editions including
- Amendments of the relevant SAA Codes of Practice, except as varied by the Contract Documents and of the
- Syl-Laws of the Local Government Authority.

 Wind loads for this project have been determined in accordance with AS1170 2 2002

 Site specific design wind speed factors adopted for this project are as follows: Importance Level = 2 c

Basic Regional Wind Speeds V500(u) = 57m/s (ultimate) V100 (p) = 48m/s (permissible V20 (s) = 38m/s (service) = 0.95Terrain / Height multiplier Mz,cat = 0.95 Shielding multiplier

Cpi = +0.0, -0.3 d Vdes = 47.1 m/s (N3) Permanent, imposed and other loads (Dead & Live) for this project have been determined in accordance with AS1170.1 - 2002 for the following loadings:

In accordance with ASTITUTE, Section 1.0 (April 1997)
Floors, self weight plus 0.5kPa distributed, gen 1.0 (Kpa to tiled areas Roofs, self weight only.

LIVE LOADS
External Floors, 4.0 (kPa distributed, 2.7 kN concentrated.

SOIL LOADS Soil Density Pressure Coefficients EARTHQUAKE

Topographic multiplier

GEOTECHNICAL

A sub-soil investigations was undertaken at this site by Tectonic Geotechnical Soil Testing report No. 17119-001-Rev0 this site has been classified as class H2 in accordance with AS2870 - 2011.

The Building Works contractor must review this report and obtain confirmation from a geotechnical engineer that the report is representative after site earthworks have been completed.

- Temporary batter slopes and positive support options for proposed excavations.
 Water table levels and if De-watering of proposed excavations is required.

A general description of various soil classification materials is listed in the following table

SITE CLASS	FOUNDATIONS
CLASS A	Mostly sand and rock sites with little or no ground movement from moisture changes.
CLASS S	Slightly reactive day sites with only slight ground movement potential from moisture changes.
CLASS M	Moderately reactive clay or silt sites which can experience moderate ground movement potential from moisture changes.
CLASS H1-H2	Highly reactive clay sites, which can experience high ground movement from moisture changes.
CLASS E	Extremely reactive sites, which can experience extreme ground movement from moisture changes.
CLASS - P	Sites which include soft soils, such as soft clay or silt or loose sanfs; uncontrolled fill; landslip risk; mine subsidence; collapsing soils; soil subject to to erosion; reactive sites subject to abnormal moisture conditions or sites which cannot be classified otherwise.

EARTHWORKS NOTES:

Where any filling is carried out on the site after the completion of the site investigation and civil earth works, the mmendation shall be followed:-

1. The site shall be stripped of all vegetation prior to the placement of any filling material.

2. Compaction Standards for filling material

A. Controlled Filing
(a) Sand filling up to 800 deep, placed in maximum 300 thick layers and compacted with a vibrating roller p achieve a minimum Dynamic Cone Penetrometer reading of 13 blows per 300 penetration 1329.F3.3). Sand fill may be flooded if necessary to achieve this compaction standard, provided the water

To a subsequently be drained from the site.

(b) Non-sand filling up to 400 deep, placed in maximum 150 thick layers and compacted with a mechanical roller. Clay fill shall be moist during compaction. (c) Controlled filling shall continue for at least 1 meter past the edge of the structure and shall be battered

back to the original surface with a slope of no more than 1:2 (Vert : to be used to be original solution with a slope of information in a control of the filling material shall be compacted as follows:Sand fill to 70% Density Index in accordance with AS1329.E6.1

Non-sand fill to 98% Maximum Dry Density (Standard Compaction) in accordance with AS1329 cl 5.4.1 Compaction tests shall be carried out on each layer as the filling is placed and results provided to the

CONCRETE NOTES:

- All workmanship and materials shall be in accordance with the requirements of the relevant current Australian Standard Codes (AS3600-2001 & AS2870-1996), Building By-Laws and the ordinances of the relevant Local Concrete Specification
- Application Conc Str (MPa) Max Slump (mm) 100 (+20, -10) Max Agg. Size (mm) Min. Cover (mm) External Slab on ground N25 Internal Slab on ground N25 External Suspended slab N32 80 (+20, -10) 80 (+20, -10) Internal Suspended slab N32

All concrete testing is to be carried out by a NATA registered laboratory, in strict accordance with the requirements of AS1012. The following minimum testing schedule is to be adopted in addition to the

- requirements of the manufacturer's quality assurance program.

 A minimum of one test (3 cylinders) to be taken from each element cast on any given day (eg. Columns,
- A minimum or one use (v)
 Section (solid) and (solid) and
- All samples are to be taken from the agitator, on site, tested by a NATA registered laboratory and results provided to the Engineer for review

 No penetrations, recesses or chases other than those shown on the structural drawings shall be made in
- concrete members without the approval of the Engineer.
- Unless noted otherwise all formed edges and corners of concrete members shall have 20mm chamfers.
 Provide drip grooves to the perimeter of the soffits of all concrete members.

CONCRETE SLABS:

- Subgrade to be proof rolled with any unsuitable material removed and replaced in accordance with
- earthworks notes.

 Any filling under slab to be placed in accordance with earthworks notes.

 Place and compact a 50mm layer of bedding sand under slab areas with 0.2mm vapor barrier over, tap and seal all joints.
- At penetrations in stabs, unless otherwise detailed reinforcement must not be cut but shall be gathered equally to each side of the penetrations and extra reinforcement provided between the penetrations as
- directed by the Engineer.

 During dry weather moisten timber formwork to assist curing of surfaces.

- Ensure no water is added to the concrete after initial batching.

 No concrete to be poured when site temperature exceeds 35° C or falls below 5° C.

 Constructions Joints or pour breaks where not shown on the approved plans or details shall be located and formed to the approval of the Engineer

- Curing by continuous wetting and/or covering for a period of not less than 7 days or by application of an appropriate sprayed membrane curing compound.
 Retain form work as long as possible on vertical surfaces

- Increased crack control methods:

 1. Use of low shrink concrete with a design shrinkage strain less than 650x10-6
- Concrete should not be placed when maximum daily temperatures are expected to rise over 30°C or when site wind speeds are expected to exceed 15 knots.

- Where floor slabs are to be tiled, the following recommendations are made, in order to minimize the effects of
- Provision of SL92 slab mesh (or equivalent)
- Placement of tiles should be delayed for as long as possible (preferably for at least 3 months)
 Use of elastic tile adhesives and provision of flexible joints between tiles at regular centers and over slab

REINFORCEMENT NOTES:

- All workmanship and materials shall be in accordance with the requirements of the relevant current Australian Standard Codes (AS3600-2001 & AS2870-1996), Building By-Laws and the ordinances of the relevant Loca
- Reinforcement is presented diagrammatically. It is not necessarily shown in true projection
- Nemorcement is presented diagrammanically. It is not necessarily shown in true projection. Provide the Engineer with 48 hours notice of reinforcement being ready for inspection. No concrete is to be poured without the prior approval of the Engineer. Splices in reinforcement shall be made only in the positions shown. Where not specified, laps shall be in accordance with AS3600 and not less than: N12 400, N16 500, N20 650, N24 -800, N28 1100, N32 1400, N36 1700.
- Welding of reinforcement will not be permitted.
- Resinforcement must not be continuous through construction joints.

 Spacement of sufficient 'stools' under main bottom and top reinforcement to allow adequate support in correct position during concreting (but not generally greater than 900mm spacings).

 Supply and lay steel fabric in flat sheets at splices. Provide 225 minimum overlap of transverse wires to all
- edges of slab fabric laps. (ie two wires of each sheet overlapping plus 25mm)
- orges of sale factor lags, liet wo wires of each sheet overlappin forovide "L' bars to all beam corners and intersections, 500 mini Reinforcement Symbols: N Grade 500 MPa Deformed Bar SL Grade 500 MPa Deformed Slab Mesh
- Grade 410 MPa Deformed Bar
- Grade 250 MPa Deformed Bar Pool Construction Grade 250 MPa Plain Bar

STRUCTURAL STEEL WORK NOTES:

All steel works is to be carried out in accordance with the current edition of:
 AS4100 - SAA steel structures code - AS1554
 SAA code for welding in buildings

SA MA 1.9 - Erection

- AISC Standardized Structural Connection.

 One full size paper copy of the shop detail drawings are to be submitted to the Engineer and approval of same obtained before commencing fabrication. Approval will not cover dimensional setout.

 Unless noted otherwise, the size of all fillet welds is to be 6mm, SP category in accordance with AS1554.
- Welding electrode grade to be E48XX unless noted otherwise.
- All bolts to be grade 8.8 high strength structural bolts to AS1525, srug tightened unless notes otherwise. Internal steel work is to be thoroughly cleaned and coated with one coat of red oxide zinc chromate paint (or treated as specified) before erection.
- treated as speciment periodic retroiting to the form of the state of t
- The steel fabricator shall provide all bolts necessary for erection of the steel work and bolt holes and cleats necessary for the work as shown, noted or implied on these drawings or the architects drawings and
- specification.

 The roof structure has been designed for normal roof loads only and does not allow for any extraneous loads.
- such as hoists, monoralis etc. except where shown on drawings.

 10. When shop splices are necessary in beams or trusses, the position and details of the splice is to be

TIMBER NOTES:

- All timber design and construction shall be in accordance with AS1720 & AS1684 U.N.O.

- All softwood shall be minimum stress grade F5 or MGP10 U.N.O.
 All hardwood shall be minimum stress grade F14 U.N.O.
 All hardwood shall be minimum stress grade F14 U.N.O.
 External timber shall be either hardwood Durability Class I or II, or impregnated grade F7 pine, pressure treated to AS1604 and re-dried prior to use. Supplementary treatment shall be applied to all cut surfaces.
- Details of preservative treatment shall be provided to the Engineer.

 All botts in timber construction shall be minimum M12 U.N.O and botts, nuts and washers shall be hot dip galvanised. Bott holes offlied in timber shall be exact size for botts and spaced as documented. Where no specified botts spacing's to be in accordance with AS1720 & As1684. Washers under bott head and nuts shall be at least 2.5 times bolt diameter.
- Bolting Schedule:

spacing M10 - 50mm M12 - 60mm M16 70mm

M20 -100mm M20 - 80mm

All bolts to timber work to be grade 4.6's u.n.o. (not applicable to masonry anchors & cast-in bolts) Bolts, nuts & washers to be hot dip galvanised. Bolt holes in steel plates shall provide a snug fit not greater than 0.5mm larger than bolt diameter. Washers to timber:

- - a. Seasoned Softwood +5.0, -0 mm . Unseasoned Softwood +3.0. -3 mm
- 10. All timber joints and notches shall be 100mm minimum away from loose knots, severe sloping grain gum
- veins or other minor defects. 11. All details not shown on the engineering drawings shall be in accordance with AS1684 - 1996 Residential
- Timber Framing Code and best practices.

 12. Roof Trusses Timber trusses shall be supplied pre-cambered by an amount equal to the applied dead load deflection. A design certificate is to be provided prior to truss manufacture and signed by Truss Engineer

(RPEQ). Once the trusses are installed the truss engineer shall provide a certificate indicating that the trusses

have been installed as required. The certificate should also indicate and cover all bracing and tie-down reg'd.



PROPOSED AMENITIES BUILDING ISAAC MOORE PARK, KENILWORTH SUNSHINE COAST REGIONAL COUNCIL

GENERAL NOTES

PRELIMINARY ISSUE FOR REPORT ONLY


....... 5576 03 C 110

Sunshine Coast Regional Council


PO Box 474, Buddina 4575, Qld


6 Innovation Parkway, Kawana Waters 4575, Qld Ph. (07) 5493 9777 Fax (07) 5493 6888 PRELIMINARY ISSUE FOR REPORT ONLY

........ 5576 03 C 200



SUNSHINE COAST REGIONAL COUNCIL





REINFORCEMENT LAPS

....500650 N16 N20800

MESH2 CROSS WIRES + 25MM






PLAN DETAILS:		PLAN AMENDMENTS:				
Designed: Drawn: Checked: Datum: Date:	SD BS RM AHD JAN 2019	Rev	Date	Comment	Altered	Chec

PROPOSED AMENITIES BUILDING ISAAC MOORE PARK, KENILWORTH SUNSHINE COAST REGIONAL COUNCIL

FOOTING & SLAB DETAILS PRELIMINARY ISSUE FOR REPORT ONLY 5576 N3 C 21N


OM Agenda Page 254 of 340 **Sunshine Coast Regional Council**

Attachment 1 Isaac Moore Park Amenities Building Plans



SAW OR TOOL JOINT


NOT TO SCALE





TYPICAL RECOMMENDED PIPE **SERVICES THROUGH FOOTING**


NOT TO SCALE


RECOMMENDATION IS MADE THAT THE HOUSE SEWER LINE UTILISE 200mm SLIPJOINTS BETWEEN JUNCTIONS











TYP. LAP ELEVATION

NOTE: 3 LAYERS OF WIRE EVEN AT CORNERS

REINFORCEMENT LAPS

N12500 N16650 N20800

MESH2 CROSS WIRES + 25MM








PROPOSED AMENITIES BUILDING ISAAC MOORE PARK, KENILWORTH SUNSHINE COAST REGIONAL COUNCIL


FOOTING & SLAB DETAILS PRELIMINARY ISSUE FOR REPORT ONLY

...... 5576 N3 C 211

Sunshine Coast Regional Council OM Agenda Page 255 of 340 SCALE 1:100



FIRST LEVEL SUSPENDED SLAB PLAN



GROUND LEVEL WALL PLAN SCALE 1:100

FIRST LEVEL BOTTOM REINFORCEMENT PLAN SCALE 1:100

FIRST LEVEL TOP REINFORCEMENT PLAN

MEMBER SCHEDULE

LEGEND

| DENOTES REIN. CONCRETE WALL UNDER

| DENOTES REIN. CONCRETE WALLS OVER

| CONCRETE WALLS
| W1 200 THICK WALL, N12-200 VERT & HORIZ, EACH FACE

REINFORCEMENT BAR LAYING SEQUENCE

(1) INDICATES LAY FIRST
(2) INDICATES LAY SECOND


TOP REINFORCMENT
(3) INDICATES LAY THIRD
(4) INDICATES LAY FOURTH

REINFORCEMENT BAR SCHEDULE

MARK	SIZE & CTRS
Α	2/S12
В	1/S12
С	N12-200
D	N12-250
E	N12-300

SUSPENDED SLAB NOTES

- 1. REFER SHEET S110 FOR GENERAL NOTES
- 2. REFER SHEET \$410 FOR DETAILS
- 3. REFER ARCHITECTURAL PLANS FOR CONFIRMATION OF ALL LEVELS, CLEARANCES, STEPS, FALLS AND SETOUT. REPORT ANY DISCREPANCIES FOR CLARIFICATION.







PROPOSED AMENITIES BUILDING
ISAAC MOORE PARK, KENILWORTH
SUNSHINE COAST REGIONAL COUNCIL

This plan is Copyright. Other than for the purposes of and subject to the conditions prescribed under the Copyright Act, no part of it may in any form or by

GROUND LEVEL WALL AND
FIRST LEVEL SUSPENDED SLAB PLAN


PRELIMINARY ISSUE FOR REPORT ONLY


...... 5576 02 S 300

Sunshine Coast Regional Council
OM Agenda Page 256 of 340


Item 8.4.2 Iconic Amenities Building - Isaac Moore Park - Kenilworth
Attachment 1 Isaac Moore Park Amenities Building Plans

NOTE: COLD JOINTS BTWN SLAB AND RC WALL TO BE ADEQUATELY WATERPROOFED TO PREVENT WATER INGRESS










SCALE 1:20

B
300


GENERAL METHOD OF WALL REINFORCEMENT

SCALE 1:20





Sunshine Coast Regional Council
OM Agenda Page 257 of 340



WALL FRAMING SCHEDULE

W2 - INTERNAL STUD

TOP PLATE 2/90x45 MGP12

90x45 MGP12 @450 CTS - 2.4m MAX 35x90 NOGGING @1350 CTS MAX

BTM PLATE 1/90x45 MGP12

W3 - SEGMENTED EXT WALL ON RAKE

TOP PLATE 2/90x45 MGP12 STUDS 90x45 MGP12 @300 CTS MAX UPPER PARAPET 600mm MAX

LENGTH 3.9m, SPAN 2.7m MAX LOWER PARAPET 600mm MAX 35x90 NOGGING @1350 CTS MAX AND AS DETAILED

BTM PLATE 2/90x45 MGP12

W4 - CIRCULAR EXTERNAL WALL TOP PLATE 92mm FLEXITRAXX

STUDS 90x45 MGP12 @300 CTS - 2.0 MAX 35x90 NOGGING @1350 CTS MAX

BTM PLATE 92mm FLEXITRAXX FULLY SUPPORTED

W5 - OVAL INTERNAL WALL TOP PLATE 92mm FLEXITRAXX

90x45 MGP12 @300 CTS 2.0 MAX 35x90 NOGGING @1350 CTS MAX BTM PLATE 92mm FLEXITRAXX FULLY SUPPORTED

ALL PLATES ARE NOT TO BE TRENCHED ALL STUDS ARE NOT TO BE NOTCHED

MEMBER SCHEDULE

W2 90 STUD VERTICAL LOAD BEARING AND BRACING WALL 6mm HARDIBOARD TO 6.0kN/m

31 JANUARY 2019

90 STUD RAKING WALL

90 STUD CIRCULAR EXTERNAL WALL

90 STUD OVAL INTERNAL WALL

75 x 5.0 SHS POST ON RAKE

RB1 150 x 75 PFC CURVED ROOF BEAM 150 x 42 LVL15 ROOF JOIST @900 CTS MAX

90 x 45 MPG12 RAFTERS @600 CTS

ROOF BATTENS

75 x 38 F11, 70 x 45 MGP12 or LYSAGHT TS40 (0.55 BMT) @900

GENERAL NOTES

REFER SHEET S110 FOR GENERAL AND OTHER NOTES. CONTRACTOR IS RESPONSIBLE FOR THE STABILITY OF THE STRUCTURE DURING CONSTRUCTION. ALL FRAMING TO BE IN ACCORDANCE WITH AS1684 - 2006 AND GENERALLY IN A TRADESMAN LIKE MANNER. ALL SCREW CONNECTIONS TO BE PRE-DRILLED.

SETOUT AND LEVELS

REFER ARCHITECT'S DRAWINGS FOR ALL LEVELS, CLEARANCES, STEPS, FALLS AND SETOUT.

TIMBER PROTECTION

ENGINEERED TIMBER PRODUCTS ARE TO BE PROTECTED FROM THE WEATHER DURING CONSTRUCTION, THOSE PRODUCTS TO BE USED IN A PERMANENT EXTERNAL ENVIRONMENT SHALL BE END AND TOP CAPPED. ALL MEMBERS SHALL BE PRIMED AND PAINTED IN ACCORDANCE WITH THE MANUFACTURERS SPECIFICATIONS TO ENSURE CONTINUED SATISFACTORY PERFORMANCE OF THE MEMBER. REFER TO MANUFACTURERS SPECIFICATIONS FOR PARTICULAR DETAILS RELATING TO INDIVIDUAL PRODUCTS

GENERAL TIE DOWN


CONTRACTOR TO ENSURE ALL TIE DOWN TO BE CONTINUOUS TO

REFER TO MANUFACTURERS SPECIFICATIONS FOR PARTICULAR PRODUCT DETAILS.

TIMBER CLASS

CLASS 3 AND 4 TIMBERS CLEAR OF THE GROUND AND EXPOSED TO THE WEATHER TO BE PRESERVATIVE TREATED TO MIN, LEVEL H3, WHERE THESE TIMBERS ARE IN CONTACT WITH THE GROUND PRESERVATIVE TREATMENT TO BE MIN. H5

FIRST LEVEL WALL PLAN




FIRST LEVEL ROOF PLAN

UPPER LEVEL WALL & ROOF PLAN





Sunshine Coast Regional Council




PROPOSED AMENITIES BUILDING ISAAC MOORE PARK, KENILWORTH SUNSHINE COAST REGIONAL COUNCIL

FIRST AND UPPER LEVEL WALL AND ROOF FRAMING PLAN

PRELIMINARY ISSUE FOR REPORT ONLY


....... 5576 03 S 400


OM Agenda Page 258 of 340







Sunshine Coast Regional Council
OM Agenda Page 259 of 340








RBI TO SPI CONNECTION





SPI TO SLAB CONNECTION

DETAIL SCALE 1:20

SCALE 1:20 A3







PROPOSED AMENITIES BUILDING ISAAC MOORE PARK, KENILWORTH SUNSHINE COAST REGIONAL COUNCIL

FRAMING DETAILS PRELIMINARY ISSUE FOR REPORT ONLY 5576 03 S 490

Sunshine Coast Regional Council OM Agenda Page 260 of 340





DETAIL SCALE 1:20

W3 - TYPICAL SEGMENTED WALL ELEVATION

SCALE 1:20





Designed:	SD	
Drawn:	BS	
Checked:	RM	
Datum:	AHD	
Date:	JAN 2019	

PLAN AMENDMENTS:							
Altered	Chec						
	_						
-							
	-						
-	1						

PROPOSED AMENITIES BUILDING ISAAC MOORE PARK, KENILWORTH SUNSHINE COAST REGIONAL COUNCIL

FRAMING DETAILS PRELIMINARY ISSUE FOR REPORT ONLY 5576 03 C 491

OM Agenda Page 261 of 340 **Sunshine Coast Regional Council**





FIGURE 1 TYPE A NAILING DETAIL

TYPICAL BRACING WALL


HARDIBRACE 6mm SHEET - 6.6kN/m

FIXING IN ACCORDANCE WITH MANUFACTURERS SPECIFICATION




SHEAR BLOCK SI - I STRAP - CAPACITY 4.9KN SHEAR BLOCK S2 - 2 STRAPS - CAPACITY 9.8 KN


(INTERNAL BRACING WALL TO EXTERNAL WALL)



SHEAR BLOCK 53 - CAPACITY 5.0 KN

(BRACING WALL PERPENDICULAR TO TRUSSES, RAFTERS OR FLOOR JOISTS)








Sunshine Coast Regional Council
OM Agenda Page 262 of 340

31 JANUARY 2019




ELEVATED WALKWAY FRAMING PLAN

SCALE 1:100






OM Agenda Page 263 of 340 **Sunshine Coast Regional Council**







SCALE 1:20 A3

SECTION SCALE 1:20



OM Agenda Page 264 of 340 **Sunshine Coast Regional Council**